
Greyter Water Ready: Greywater Tied into 3" Waste Stack



- 1. Isolate greywater -2 Showers
- Homerun greywater to mechanical room -2" drain ties into 3" waste stack at the lowest point (4"x4"x2" wye connection with cleanout)
 Isolate supply lines to toilets

- 4. Have vent accessible for future use (capped or tied into greywater line)
 5. Single gang 15Amp, 120V plug located near 2" greywater drain, 48" above finished floor

